

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-00477-00-02  
Spot: SWSESE Sec/Twnshp/Rge: 15-13S-21W  
330 feet from S Section Line, 990 feet from E Section Line  
Lease Name: MUHLEIM B Well #: 1  
County: TREGO Total Vertical Depth: 3905 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 1019  
HAYS, KS 67601

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 5.5   | 3904       |             | 175 SX   |
| SURF   | 8.625 | 246        |             | 170 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/27/2012 12:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: TERRY PIESKER Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 735-4363

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 11 sx gel.  
Shot perforations at 240', 935', 1590' and 1900'.  
Perforations at 3904' - 3905'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/27/2012 5:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3670' and pumped 11 sx gel followed by 75 sx cement w/200# hulls.  
Pulled tubing to 2195' and pumped 270 sx cement w/200 # hulls. Good circulation of cement.  
Pulled tubing out. Tied on to casing and squeezed with 30 sx cement. Shut in pressure 500 psi.  
Back side full of cement. 500 psi.

Perfs:


| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3904 | 3905 |      |          |

Remarks: ALLIED CEMENT TICKET # 56598

Plugged through: TBG

RECEIVED  
JAN 07 2013  
KCC WICHITA

District: 04

Signed:  (TECHNICIAN)

CM

DEC 27 2012