

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21193-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 14-13S-21W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: SCHMEIDLER Well #: 2
County: TREGO Total Vertical Depth: 3862 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3824		
PROD	4.5	3849		500 SX
SURF	8.625	263		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/27/2012 12:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY PIESKER Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 735-4363

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Shot Perforations at 260', 885', 1550' and 1850'.
Perforations at 3468' - 3471', 3485' - 3488', 3520' - 3524', 3560' - 3564', 3643' - 3646' and 3849' - 3862'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/27/2012 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3606' and pumped 100 sx cement w/250 # hulls.
Pulled tubing to 2254' and pumped 175 sx cement w/50 # hulls. Good circulation on cement.
Pulled tubing out and topped off with 20 sx cement.
Tied on to back side and squeezed with 5 sx cement. Shut in pressure 200 psi.
GPS: 38.92255 -099.62160

Perfs:

Top	Bot	Thru	Comments
3849	3862		
3643	3646		
3560	3564		
3520	3524		
3485	3488		
3468	3471		

RECEIVED
JAN 07 2013

Remarks: ALLIED CEMENT TICKET # 56597

KCC WICHITA

Plugged through: TBG

District: 04

Signed [Signature] (TECHNICIAN) CM

DEC 27 2012