

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

** 1 IMAGE ONLY - CANNOT INV.*
API Well Number: 15-203-20129-00-00 *AS PLUG DT. EXCEEDS 5 YR. CMT. OFF.*
Spot: E2NESE Sec/Twnshp/Rge: 26-20S-35W
1980 feet from S Section Line, 330 feet from E Section Line
Lease Name: BRACK Well #: 1
County: WICHITA Total Vertical Depth: 5100 feet

Operator License No.: 31093
Op Name: BECKER OIL CORPORATION
Address: PO BOX 1150
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	307	0	

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/24/1997 9:30 PM
Plug Co. License No.: 5382 Plug Co. Name: CHEYENNE DRILLING, INC.
Proposal Revd. from: PHIL LLOYD Company: CHEYENNE DRILLING, INC. Phone: (620) 277-2062

Proposed Plugging Method: TO FILL HOLE WITH HEAVY MUD & SPOT CEMENT THROUGH DRILL PIPE. 1ST PLUG AT 2300' WITH 50 SX CMT. 2ND PLUG AT 1150' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 40 SX CMT. 4TH PLUG AT 330' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE
Date/Time Plugging Completed: 11/25/1997 10:00 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

1ST PLUG AT 2250' WITH 50 SX CMT. 2ND PLUG AT 1150' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 40 SX CMT. 4TH PLUG AT 330' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: DP

District: 01

Signed

Scott Alberga
(TECHNICIAN)

RECEIVED
NOV 14 2012
KCC WICHITA

mmx