

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05180-00-00
Spot: NENWSW Sec/Twnshp/Rge: 4-15S-12W
2310 feet from S Section Line, 990 feet from W Section Line
Lease Name: KUHNLE Well #: 11
County: RUSSELL Total Vertical Depth: 3080 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3078		75 SX
SURF	8.625	1		1 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/07/2012 12:00 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: VAL DREHER Company: JOHN O. FARMER, INC. Phone: (785) 483-3144

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforated casing at 1500', 730', 450' and 150'.
Reordered 150 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/07/2012 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2900' and pumped 100 sx cement w/300 # hulls.
Pulled tubing to 1940' and pumped 125 sx cement w/300 # hulls.
Pulled tubing to 850' and pumped 125 sx cement.
Lost circulation.
POOH and WOC. Reordered 150 sx cement w/300 # hulls.
Ran tubing to 1500' and pumped 65 sx cement w/300 # hulls. Good circulation of cement to the pit.
POOH. Hooked up to casing and pumped 40 sx cement at 200 psi. Shut in well.
12/07/12- Top of cement at 200'. Quality cementing topped off well with cement.

Perfs:

Top	Bot	Thru	Comments
3051	3063		
3038	3042		
3025	3031		
2982	2990		

RECEIVED
DEC 19 2012
KCC WICHITA

Remarks: QUALITYCEMENTING TICKET # 6218

Plugged through: TBG

District: 04

Signed Ray Dinkel
12/27/12 (TECHNICIAN)

CM

DEC 11 2012