

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-193-20875-00-00  
Spot: NENESE Sec/Twnshp/Rge: 27-10S-35W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease Name: ROSIE Well #: 1-27  
County: THOMAS Total Vertical Depth: 4950 feet

Operator License No.: 8628  
Op Name: FORESTAR PETROLEUM CORPORATIO  
Address: 1801 BROADWAY # 900  
DENVER, CO 80202

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 303        |             | 185 sx   |

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2012 12:00 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: MARK Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE  
Date/Time Plugging Completed: 12/11/2012 12:15 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

1st plug @2830 w/25 sx  
2nd plug @2100 w/100 sx  
3rd plug @360 w/40 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

District: 04

Signed Bruce Rodie  
12/24/12 (TECHNICIAN) CR

RECEIVED  
DEC 19 2012  
KCC WICHITA

DEC 13 2012