

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21863-00-00
Spot: W2SESENW Sec/Twnshp/Rge: 23-22S-25W
2310 feet from N Section Line, 2199 feet from W Section Line
Lease Name: SCHMITT Well #: 4-23
County: HODGEMAN Total Vertical Depth: 4730 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	607		WITH 345 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/04/2012 7:30 PM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: UVALDO MARTINEZ Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 850' WITH 40 SX CMT. 3RD PLUG AT 640' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 12/04/2012 10:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 850' WITH 40 SX CMT. 3RD PLUG AT 640' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY BASIC ENERGY.

Plugged through: DP

RECEIVED
DEC 13 2012
KCC WICHITA

District: 01

RECEIVED

DEC -7 2012

KCC DODGE CITY

Signed

Richard W. Lacey

12/27/12 (TECHNICIAN)

R 18