

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20931-00-01
Spot: NESE Sec/Twnshp/Rge: 29-32S-29W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: RICHARD ROBERTS Well #: 1
County: MEADE Total Vertical Depth: 5802 feet

Operator License No.: 33649
Op Name: KENNETH W. CORY, LTD.
Address: 6750 W. LOOP SOUTH, STE 1050
BELLAIRE, TX 77401

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5438		WITH 2 SX CMT
PROD	5.5	5787	2361	WITH 150 SX CMT
SURF	8.625	1537		WITH 724 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/07/2012 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MARK HORNEY Company: KENNETH W. CORY LTD Phone: (713) 661-5911

Proposed Plugging Method: SET CIBP @ 5454' WITH 2 SX CMT. PLUG AT 1560' WITH 10 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 12/07/2012 10:45 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 5438' WITH 2 SX CMT. 1ST PLUG AT 1562' WITH 10 SX GEL & 50 SX CMT.
2ND PLUG AT 542' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 22 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5532	5533		
5515	5518		
5504	5509		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

DEC -7 2012

KCC DODGE CITY

Signed

K M SM
12/24/12

(TECHNICIAN)

RECEIVED
DEC 13 2012

KCC WICHITA

AND