

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21347-00-00  
Spot: NENESWSW Sec/Twnshp/Rge: 18-28S-17W  
1331 feet from S Section Line, 4038 feet from E Section Line  
Lease Name: BYRD HARDY Well #: 2  
County: KIOWA Total Vertical Depth: 4900 feet

Operator License No.: 6926  
Op Name: ADVANTAGE RESOURCES, INC.  
Address: 1775 SHERMAN ST STE 1700  
DENVER, CO 80203

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4888	2400	WITH 195 SX CMT
SURF	8.625	474		WITH 280 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/05/2012 10:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 4770' & CAP WITH 2 SX CMT. PLUG AT 1170' WITH 12-15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/05/2012 11:50 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SANDED TO 4770' & CAPPED WITH 2 SX CMT. 1ST PLUG AT 1165' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 520' WITH 50 SX CMT. 3RD PLUG AT 43' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4838	4841		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed

*[Signature]*  
12/7/12

(TECHNICIAN)

RECEIVED

DEC -7 2012

KCC DODGE CITY

Form CP-2/3

RECEIVED  
DEC 13 2012  
KCC WICHITA

*[Handwritten mark]*