

*CANNOT INV. AS
* IMAGE ONLY - PLUG DT. EXCEEDS
5 YR. CUTOFF.*

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20042-00-00
Spot: SWSENE Sec/Twnshp/Rge: 33-23S-4W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: DAISEY E PIERCE Well #: 3
County: RENO Total Vertical Depth: 3677 feet

Operator License No.: 5330
Op Name: EXCALIBUR PRODUCTION COMPANY,
Address: 1016 N MAIN PO BOX 278
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	3672	896	
SURF	10	247		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/1995 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DENNIS GORDLY Company: EXCALIBUR PRODUCTION CO Phone: (316) 241-1265

Proposed Plugging Method: SAND TO 3290' AND TOP WITH 10 SKS CMT. SHOOT PIPE OFF AND PULL SAME TO 600'. SPOT 35 SKS. CMT. PULL PIPE TO 375' AND CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/18/1995 12:00 AM KCC Agent: JEFF KLOCK

Actual Plugging Report:
SANDED TO 3290' AND TOPPED WITH 10 SKS CMT. SHOT PIPE OFF @ 897', PULLED PIPE TO 613' AND SPOTTED 35 SKS CMT. PULLED PIPE TO 390' AND CIRCULATED 175 SKS CMT. CEMENT DID NOT COME TO SURFACE. RAN WIRELINE TO TOP OF CMT @ 244'. RAN 2" TUBING TO TOP OF CMT. AND CIRCULATED 100 SKS CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3348	3353	CSG	

RECEIVED
NOV 09 2012

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED #2834 & #2835
Plugged through: CSG

KCC WICHITA

District: 02 Signed Jeff Klock
(TECHNICIAN)