

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23184-00-00
Spot: SWNNWN Sec/Twnshp/Rge: 19-32S-5E
3974 feet from S Section Line, 4879 feet from E Section Line
Lease Name: PAYNE Well #: 4
County: COWLEY Total Vertical Depth: 3480 feet

Operator License No.: 33277
Op Name: COOPER, ALBERT L.
Address: PO BOX 381
WINFIELD, KS 67156

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-------------|
| CIBP | 4.5 | 2400 | | |
| PROD | 4.5 | 3470 | | 175 SXS CMT |
| SURF | 8.625 | 150 | | 130 SXS CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2012 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE COMPANY Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 12/07/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 1511', TAGGED SOLID. LAYED DOWN TBG. SANDED BACK @ 1450', 11-21-2012, DUMP BAILED 5 SXS CEMENT ON TOP. 11-26-2012, TAGGED BOTTOM CEMENT PLUG @ 1375'. 11-28-2012, CUT CASING @ 548', LAYED DOWN CASING. 12-7-2012, RIH W/TBG @ 255', COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 105 SXS 60/40 POZMIX 4% GEL TO SURFACE, LAYED DOWN TBG. CEMENT CIRCULATED. PLUG DOWN 12-7-2012 @ 5:00 PM. COPELAND ACID SERVICE CEMENT TICKET #41739.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2384 | 2390 | CSG | LAYTON |

RECEIVED
DEC 17 2012

Remarks: COMPLIANCE PLUGGING/ TA

Plugged through: TBG

KCC WICHITA

District: 02

Signed Jeff Klock
12/07/12 (TECHNICIAN)