

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21265-00-01 \* IMAGE ONLY - CANNOT INV. AS PLUG DT. EXCEEDS 5 YR. CUTOFF.  
Spot: E2SWSW Sec/Twnshp/Rge: 16-25S-9W  
660 feet from S Section Line, 4300 feet from E Section Line  
Lease Name: SCHOOL Well #: 1  
County: RENO Total Vertical Depth: 4007 feet *VW 74*

Operator License No.: 30146  
Op Name: MACH PETROLEUM, INC.  
Address: PO BOX 35583  
TULSA, OK 74153

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4007	2960	
SURF		200		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/25/1994 12:00 AM  
Plug Co. License No.: 6050 Plug Co. Name: KELSO CASING PULLING, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JACK LUTHI Witness Type: NONE  
Date/Time Plugging Completed: 07/26/1994 12:00 AM KCC Agent: JEFF KLOCK

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_  
SHOT WELL @ 2960', PIPE CAME LOOSE. PULLED TO 1400', PUMPED 35 SKS CEMENT. PULLED 825' PUMP 35 SKS CEMENT. PULLED TO 250' CIRCULATED 85 SKS CEMENT TO SURFACE. PULLED REST OF PIPE, TOPPED OFF WITH 10 SKS CEMENT. 60/40 POZ 4% GEL. PLUGGING COMPLETE.

Remarks: \_\_\_\_\_  
Plugged through: CSG

RECEIVED  
NOV 09 2012  
KCC WICHITA

District: 02 Signed Jeff Klock  
(TECHNICIAN)