

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-00314-00-00  
Spot: SE Sec/Twnshp/Rge: 10-22S-34W  
1324 feet from S Section Line, 1331 feet from E Section Line  
Lease Name: MILLER Well #: 1  
County: FINNEY Total Vertical Depth: 2610 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1100		
CIBP		2500		WITH 2 SX CMT
PROD	5.5	2560	0	
SURF	8.625	285		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2012 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 2500' WITH 2 SX CMT. SET CIBP @ 1100'. LOAD HOLE & PRESSURE TEST. RUN BOND LOG. PERFORATE 5 1/2" @ 1080'. RUN TBG TO 1080' & FILL 5 1/2" X 8 5/8" TO SURFACE WITH CMT. IF CMT DOES NOT CIRCULATE UP 8 5/8" X 5 1/2" ANNULUS. PUMP 150 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/19/2012 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2500' WITH 2 SX CMT. CIBP @ 1100'. LOAD & TEST CASING TO 750#.  
HOLDING. RAN BOND LOG FROM 1100' TO 0'. TOP OF CMT @ 840'. PERFORATE 4  
HOLES @ 700'. TAKE INJECTION TEST DOWN 5 1/2" CASING. CIRCULATE CMT  
FROM 700' TO 0' WITH 205 SX CMT LEAVING CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2560	2610	OH	

RECEIVED  
JAN 11 2013  
KCC WICHITA

Remarks: CONTROL # 20120064 001 USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED  
DEC 31 2012  
KCC DODGE CITY

Signed

*Ken Jehlik*  
(TECHNICIAN)