

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20540-00-00
Spot: SESWSW Sec/Twnshp/Rge: 14-14S-15W
343 feet from S Section Line, 4353 feet from E Section Line
Lease Name: SMITH A Well #: 6
County: RUSSELL Total Vertical Depth: _____ feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3222		
SURF	8.625	215		160 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/05/2012 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD O MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 257-3409

Proposed Plugging Method: Ordered 225 sx 60/40 pozmix 4% gel cement
11/06/2012-Ordered 250 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2012 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran 3 drill collars in with bit and sub in well. Got down to 825' with trouble and hung up the collars. Worked free and spotted 125 sx cement. Pulled drill collars out and shut down.
11/06/2012-Ran tubing to 630'. Tagged up and pumped 50 sx cement. Cement circulated out of casing.
Pulled tubing to 280'. Cellar was losing fluid. Pumped 40 sx cement w/200 # hulls. Cement circulated.
POOH and topped off cellar with 10 sx cement. Checked on 11/07/2012 and cellar/well was full.

GPS: 38.82823 -098.96260

Perfs:

RECEIVED
NOV 29 2012
KCC WICHITA

Remarks: QUALITY WELL SERVICES TICKET # 5718 CONTROL # _____ SMITH A FEE FUND PROJECT

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

NOV 20 2012