

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20990-00-00
Spot: SWNESW Sec/Twnshp/Rge: 14-14S-15W
1460 feet from S Section Line, 3489 feet from E Section Line
Lease Name: SMITH Well #: 9
County: RUSSELL Total Vertical Depth: 3250 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3249		175 sx
SURF	8.625	628		280 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2012 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCLANTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 257-3409

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls and 10 sx gel.
Perforations: 1603', 913' and 403'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2012 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3200' and pumped 10 sx gel followed by 50 sx cement w/100 # hulls.
Pulled tubing to 1650' and pumped 100 sx cement w/200 # hulls.
Pulled tubing to 650' and pumped 70 sx cement. Cement circulated.
POOH. Hooked to casing and pumped 60 sx cement with no pressure. Pumped 20 sx cement w/50 # hulls at 250 psi. Shut in.
Braden head was dug out and found to be full of cement.

GPS: 38.83130 -098.95952

Perfs:

RECEIVED
NOV 19 2012
KCC WICHITA

Remarks: QUALITY WELL SERVICES TICKET # 5721 CONTROL # 20130013-004 FEE FUND PROJECT SMITH A

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

NOV 13 2012

Form CP-2/3