

JAN 25 2013

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC Chanute Dis. Form CP-4 March 2009 Type or Print on this Form Form must be Signed and dated by the filer

15-073-19524-00-00

OPERATOR: License #: 33913 Name: Winterscheid Oil LLC Address 1: 764 Rd 70 City: Olpe State: KS Zip: 66865 Contact Person: Don Winterscheid Phone: (620) 678-3249 Type of Well: (Check one) [X] Oil Well [ ] Gas Well [ ] OG [ ] D&A [ ] Cathodic [ ] Water Supply Well [ ] Other: [ ] SWD Permit #: [ ] ENHR Permit #: [ ] Gas Storage Permit #: [ ] Is ACO-1 filed? [ ] Yes [ ] No If not, is well log attached? [X] Yes [ ] No Producing Formation(s): List All (If needed attach another sheet) Lime Depth to Top: 1355' Bottom: 1365' T.D. Lime Depth to Top: 1557' Bottom: 1605' T.D.

API No. 15 - 02-06-1938 NE NW SE 17-24-13E Spot Description: NE NW SE 17-24-13E Sec. 17 Twp. 24 S. R. 13 [X] East [ ] West 750 2020 Feet from [X] North [ ] South Line of Section 540 2199 Feet from [ ] East [X] West Line of Section Footages Calculated from Nearest Outside Section Corner: [ ] NE [ ] NW [ ] SE [ ] SW County: Greenwood Lease Name: Erickson Well #: 2 Date Well Completed: 2-25-1938 The plugging proposal was approved on: 2-25-1938 (Date) by: Mike Heffron (KCC District Agent's Name) Plugging Commenced: 1-08-2013 Plugging Completed: 1-18-2013

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Includes a RECEIVED FEB 06 2013 KCC WICHITA stamp.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set. TD 1621'. Set bottom bridge in 7" @ 1560'. Dumped 5 gal large rock. Then dumped 6 gal of chat. Let set over night. Mixed and dumped 8 sks portland cement on 1560'. Ran in 18 jts of 2 3/8" tubing and pumped in 25 sks of cement w/gel. Pulled up tubing to 210' and pumped cement to surface. Pulled out and ran 2 3/8" tubing on outside of 7". Cemented to surface. Came back to check fill-up. Mixed and topped out 7". w/3 sks of portland cement. Checked 7" next morning. Mixed and dumped 2 sks. of portland cement on top. 6112

Plugging Contractor License #: Name: Long Drilling Company LLC Address 1: PO Box 131 Address 2: City: Hamilton State: KS Zip: 66853 + 0131 Phone: (620) 678-3461 Name of Party Responsible for Plugging Fees: Winterscheid Oil LLC State of Kansas County: Greenwood ss. Patricia Reed (Print Name) [ ] Employee of Operator or [X] Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: \_\_\_\_\_

Handwritten mark or signature.

