

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-116-20442-000

LEASE NAME Shade #2

WELL NUMBER _____

SPOT LOCATION NW SE SW

SEC. 5 TWP. 16S RGE. 16W (P) or (W)

COUNTY Rush

Date Well Completed _____

Plugging Commenced 6/25/84

Plugging Completed 7/23/84

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Rains & Williamson Oil Co., Inc.
 ADDRESS 435 Page Court Bldg, 220 W. Douglas, Wichita, Ks. 67202

PHONE # 310 265-9686 OPERATORS LICENSE NO. # 5146

Character of Well _____
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3497'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8		none
				5 1/2"	3496'	2327'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each snt.
Plugged bottom with sand to 3450' & 5 sacks cement. Shot pipe at 2613' 2515' 2418', & 2325'. Pulled total of 72 joints of pipe. Plugged well with 2 hulls, 10 gel, 50 cement, 7 gel, 1 hull, released plug, & 120 sacks 60/40 poz 2% gel 3% c.c. down 8 5/8
Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
 Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature: R. Darrell Kelso)

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1984


 IRENE HOOVER
 State of Kansas
 My Comm. Exp. Aug. 15, 1985

Irene Hoover
 Notary Public

My Commission expires:

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 26 1984
 CONSERVATION DIVISION
 Wichita, Kansas