

1 030427

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,173-~~0000~~
NE SW SW, SEC. 26, T 17 S, R 28 W/E
990 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5068

Lease Name Hartman Well # 1

Operator: Thomas E. Black
Name & Address 527 Union Center Building
Wichita, KS 67202

County Lane (Mississippi) 148.85
Well Total Depth 4580 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8" feet 307

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor B & B Drilling, Inc. License Number 5110

Address 501 Union Center, Wichita, KS 67202

Company to plug at: Hour: 10:00 am Day: 27 Month: May Year: 19 85

Plugging proposal received from John Armbruster

(company name) B & B (phone) 316-267-0613
Elevation 2670

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2070

- 1st plug at 2100' with 50 sx cement 2nd plug at 1020' with 75 sx cement
- 3rd plug at 600' with 50 sx cement 4th plug at 330' with 40 sx cement
- 5th plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 7th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:30 am Day: 27 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1020' with 75
sx cement, 3rd plug at 600' with 50 sx cement, 4th plug at 330' with 40 sx cement, 5th &
6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,
7th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1985
5-31-85

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

INVOLVED

(operator did not) observe this plugging.

DATE 6-6-85

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 8336
5-27

JUL 12 1985 AUG 22 1985
2nd