

To: 1 070304
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address 125 N. Market, Suite 1000
Wichita, KS 67202

85
API NUMBER 15-101-21,357-0000

SE SE SE, SEC. 26, T 17 S, R 28 (W/8)
330 feet from S section line
330 feet from E section line
Lease Name Ken Hartman Well # 1
County Lane 1-51.16
Well Total Depth 4651 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033
Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 11 p.m. Day: 6 Month: 2 Year: 19 87

Plugging proposal received from Ed McKenna

(company name) Murfin Drilling Company (phone) 308-345-5010

were: to fill hole with heavy mud and spot cement through drill pipe. Elevation 2715'
Anhydrite 2100-30'

1st plug at 2140' with 50 sx cement, 2nd plug at 1300' with 100 sx cement,

3rd plug at 287' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 15 sx cement.

Plugging Proposal Received by Jack Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:30 a.m. Day: 7 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2140' with 50 sx cement,

2nd plug at 1300' with 100 sx cement,

3rd plug at 287' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby certify that I have observed this plugging.

DATE 2-20-87

INV. NO. 16187

Signed Dan Jordan
(TECHNICIAN)