

To: 1 070903
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-8 21 P
API NUMBER 15- 101-20,344-0000
NW SE SW, SEC. 27, T 17 S, R 28 W/E
990 feet from S section line
3630 feet from E section line
Lease Name Cartmill "B" Well # 1
County Lane 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 258

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393
Operator: A.L. Abercrombie, Inc.
Name & Address Rt 1, Box 56
Great Bend, KS 67530

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor A.L. Abercrombie, Inc. License Number 5393
Address Rt. 1, Box 56, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 8 Month: 1 Year: 19 91

Plugging proposal received from R.D. Rapp
(company name) A.L. Abercrombie, Inc. (phone) 316-793-8186

were: 4 1/2" at 4577' w/200 sx cement, PBD 4539', Perfs at 4224-26'
1st plug pump 400 lbs. hulls and 20 sx cement,
2nd plug perforate at 1485', pump 150 sx cement down 4 1/2",
3rd plug pump 130 sx cement down backside.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 8 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 400 lbs. hulls and 20 sx cement,

2nd plug perforated at 1485', pumped 150 sx cement down 4 1/2", Maximum pressure 800 psi
and shut in 300 psi.

3rd plug pumped 130 sx cement down backside, Maximum pressure 100 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 2-8-91

INV. NO. 30617

Signed Dan Goodrow
(TECHNICIAN)