



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 27 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Powell of Braden-Deem has this

date requested permission to plug the following described well:

Mr. Powell guarantees payment of the plugging fee.

Operator's full Name: Braden-Deem Inc

Complete Address: 200 E 1st, Wichita, Kansas

Lease Name: G. Miller "B" Well No. 1

Location: SW NE Sec. 12 Twp. 22 Rge. 23 ~~(E)~~ (W)

County: Hodgeman Total Depth 4563' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Powell was instructed to plug the well as follows:

9 5/8" to 257' circulated w/ cement. 7" to 4555' cemented.

Open hole 4555' to 4563' Plug bottom w/ sand & 5 sacks cement

Top of cement 4500' Mud 4500' to 700'

Spot 70 sacks cement 700' to 400' Mud 400' to 200'

Plug & 50 sacks cement 200' to 0'.

Very truly yours,

Conservation Division Agent