

State of Kansas



15-155-01648-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
CORPORATION COMMISSION

JUN 23 1967
6-23-67

CONSERVATION DIVISION
Wichita, Kansas

June 12, 1967

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name: Henry Well No. 4

Location: C SE SE Sec. 17 Twp. 22 Rge. 8 (E) (W) X

County Reno Total Depth 3560' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

Fill hole with sand to 3525' and cement with 5 sacks.

Fill hole with mud to 225'. Set rock bridge from 225' to 215' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent