

State of Kansas



FORM - CP-2

15-033-00093-0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Hopkins of Aylward Drilling Co. has this

date requested permission to plug the following described well:

Mr. Hopkins guarantees payment of the plugging fee.

Operator's full Name: Aylward Drilling Co.

Complete Address: 909 1st National Bank Bldg., Wichita, Kans.

Lease Name: Yost Well No. # 1

Location: C SW SE Sec. 6 Twp. 31 Rge. 17 (E) (W) W

County Comanche Total Depth 5472 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hopkins was instructed to plug the well as follows:

293' of 8 5/8" surface pipe, cemented with 275 sacks. Fill
hole with drilling mud to 280', 1st cementing plug, bridge
with hulls, cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, cement
with 10 sacks to base cellar. Bridge and cement rat hole
with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent