



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

April 25, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Co. has this
date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Inc.

Complete Address: Box 169, Russell, Kansas 67665

Lease Name: G. Becker "A" Well No. 1

Location: SW SW SE Sec. 2 Twp. 17 Rge. 9 (BX(W) X

County: Ellsworth Total Depth 3245' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lynch was instructed to plug the well as follows:

Fill hole with sand to 3230' and cement with 5 sacks cement.

Fill hole with mud to 269'. Set rock bridge from 269' to 260' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock
bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent