



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 1 1964

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Borne of Morrison Producing Co. has this date requested permission to plug the following described well:

Mr. Borne guarantees payment of the plugging fee.

Operator's full Name: Morrison Producing Co.

Complete Address: Drawer 712 Eldorado, Kansas

Lease Name: Hammeke Well No. # 1

Location: C NE 1/4 NW 1/4 Sec. 34 Twp. 25 Rge. (E) (W) 21

County Ford Total Depth 4844 Oil Well x

Gas Well Input Well SWD Well D & A x Lost Hole

Mr. Borne was instructed to plug the well as follows:

7"-352' Circulated w/cement.

Mud 4844' to 700' Spotted 10 Sx. cement 700' to 640'

Mud 640' to 350' Spotted 10 Sx. cement 350' to 290'

Mud 290' to 35' Plug, Hulls, 5 Sx. cement 35' to 0

Very truly yours,

[Signature]
 Conservation Division Agent