



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg.
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 1-26-68
 JAN 26 1968
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

January 16, 1968

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name: Grover Well No. 1

Location: C NE NW Sec. 20 Twp. 22 Rge. 8 (E) (W) X

County: Reno Total Depth 3605' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

- Fill hole with sand to 3525' and cement with 5 sacks.
- Fill hole with mud to 220'. Set rock bridge from 220' to 210' and
- cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge
- from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent