



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

June 3, 1972

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jerb Ogle of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Bell Oil Company (Bell-Thompson-Stephenson)

Complete Address: 562 Wetmore Court, Wichita, Kansas 67209

Lease Name: Nienke Well No. 1

Location: NW SE SW Sec. 22 Twp. 15 Rge. 8 ~~(E)~~ (W) X


County: Ellsworth Total Depth 3060' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

Fill hole with mud to 265'. Push plug and 1/4 sack hulls to 265' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent