



15-033-3000a-000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1965
07-16-65

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Dale Roberts of Stickle Drilling Company has this date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Company

Complete Address: 300 Union National Bldg., Wichita, Ks.

Lease Name: Muriel Gregg Well No. # 1

Location: C NW SE Sec. 31 Twp. 33 Rge. 16 (E) (W) W

County Comanche Total Depth 5831' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

227' of 13 3/8" surface pipe, cement circulated with 250 sacks.
Fill hole with drilling mud to 225', 1st cementing plug, bridge
with hulls, and cement with 50 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 20 sacks to baase cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,
Archie Elving