

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-033-00095-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. W. L. Barnett of D & M Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Barnett guarantees payment of the plugging fee.

Operator's full Name: Ferguson Oil Company

Complete Address: 522 Union Center, Wichita, Kansas

Lease Name: Herd Well No. # 1

Location: C NE SW Sec. 34 Twp. 32 Rge. 19 (E) (W) W

County Comanche Total Depth 5348 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Barnett was instructed to plug the well as follows:

409' of 13 3/8" surface pipe, cement circulated with 450
sacks. Fill hole with drilling mud to 300', 1st cementing
plug, bridge with hulls, and cement with 40 sacks. Fill hole
with drilling mud to 40', 2nd cementing plug, bridged with
hulls, and cement with 20 sacks, to base cellar. Bridge rat
and mouse hole, and cement with 4 sacks.

Very truly yours,

Archie Elving