



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

Sept. 12, 1981

Comp. Plug ^{1:45 AM} _{Wed} 13 day 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)
15-033 - 20450

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1981

Dear Sir:

Mr. Don Jenkins of Hickman Drilling Co. has this in Wichita, Kansas

date requested permission to plug the following described well:

Operator's Full Name: K. R. M. Petroleum Corporation

Complete Address: 820 Guaranty Bank Bldg 817, 17th St. Denver Colo 80202

Lease Name: Kerstetter Well No. 1-33

Location: C NW NE Sec. 33 Twp. 32 Rge. 19 W (E) (VA)

County: Comanche Total Depth: 5220'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Jenkins was instructed to plug the well as follows:

There is 676' of 8 5/8" of surface casing cement circulated with 400 skt of cement. They had hole full of heavy mud. 1st plug pushed rubber plug to 650' and put 40 skt of cement on top of rubber plug. 2nd plug with hole full of heavy mud put 1 skt of hulls at 40' to make solid bridge & put 10 skt of cement on top of bridge. Cement from 40' to 0'. They 5 skt in rat hole + 5 skt in mouse hole. Plugging accomplished by Halliburton Co.

Very truly yours,

Paul Luthie
Conservation Division Agent