

State of Kansas



15-159-02889-0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 0.1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date July 26, 1962, authorized

The following plugging operation:

Operator's full Name: Muir-Thompson, Inc.

Complete Address: 201 Garlinghouse Bldg., Topeka, Kansas

Lease Name: Kelly Well No. 1

Location: NE SE NW Sec. 22 Twp. 20 Rge. 10 (E) (W)

County Rice Total Depth: 3402

Oil Well Gas Well Input Well SWD Well

D & A Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Circulate heavy mud. Fill hole to 175' with heavy mud.

Push plug and 1/4 sack hulls to 175' and cement with 20 sacks
thru drill pipe. Fill hole to 40' with heavy mud. Push plug
and 1/4 sack hulls to 40' and cap with 10 sacks.

Fill, bridge, and cement rathole with 2 sacks.

Very truly yours,

