

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20826-00-01
Spot: N2NENW Sec/Twnshp/Rge: 9-12S-22W
330 feet from N Section Line, 1980 feet from W Section Line
Lease Name: BABB Well #: 21-9
County: TREGO Total Vertical Depth: 4126 feet

Operator License No.: 9152
Op Name: MAREXCO, INC.
Address: 3033 NW 63RD ST - STE 151
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	4.5	1751		335 SX
PROD	4.5	4126		460 SX
SURF	8.625	206		185 SX
T1	2.375	4038		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2012 8:45 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: KELLY BRANUM Company: MAREXCO, INC. Phone: (785) 483-2662

Proposed Plugging Method: Ordered 275 sx cement, 600 # hulls and 15 sx gel.
PBTD at 4086'.
Fluid level shot by Kelly Branum. Found to be 4000' down to top of fluid.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/18/2012 8:45 AM KCC Agent: RAY DINKEL
12:30 pm

Actual Plugging Report:

Hooked up to 5 1/2" casing. Found out later one 5 1/2" joint was run to land casing because of a braden head slip and work over head.
Pumped 50 sx cement w/200 # hulls followed with 15 sx gel followed by 100 sx cement.
Maximum pressure 1250psi. Shut in pressure 500 psi.
Hooked to braden head and pumped 30 sx cement at 300 psi.
GPS: 39.02932 -099.77183

Perfs:

Top	Bot	Thru	Comments
4008	4040		

RECEIVED
JAN 08 2013
KCC WICHITA

Remarks: CONSOLIDATED OIL WELL SERVICE TICKET # 39170

Plugged through: CSG

District: 04

Signed Ray Dinkel
12/18/12 (TECHNICIAN)

CM

DEC 26 2012