

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20351-00-00
Spot: NWNWSWSW Sec/Twnshp/Rge: 10-21S-32W
1294 feet from S Section Line, 5182 feet from E Section Line
Lease Name: KOSTER Well #: 1
County: FINNEY Total Vertical Depth: 1850 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1844	0	WITH 300 SX CMT
SURF	7	366		WITH 100 SX CMT

Well Type: SWD UIC Docket No: D19782.0 Date/Time to Plug: 12/14/2012 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0806

Proposed Plugging Method: TOOH W/TBG & PACKER (IF POSSIBLE). TAKE INJECTION TEST DOWN 4 1/2". PUMP 300# HULLS IN 120 SX CMT & LEAVE CASING FULL OF CMT. ATTEMPT TO PUMP DOWN 4 1/2" X 7" ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/14/2012 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CEMENT FROM 1720' TO 0' USING 150# HULLS & 115 SX CMT. PRESSURE TO 1200#. HOLDING. ATTEMPT TO PUMP DOWN ANNULUS. COULD NOT @ 600#. FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
1680	1720		

RECEIVED
JAN 11 2013
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
12/30/12
(TECHNICIAN)
cc TO MIC 1/11/13

RECEIVED

DEC 27 2012

KCC DODGE CITY

AWY