

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-03692-00-01
Spot: NWNWNWSE Sec/Twnshp/Rge: 17-25S-1E
2332 feet from S Section Line, 2366 feet from E Section Line
Lease Name: HALEY Well #: 1
County: SEDGWICK Total Vertical Depth: 3048 feet

Operator License No.: 6804
Op Name: LACHENMAYR OIL LLC
Address: PO BOX 526
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		2980		PACKER TYPE AND SETTING DEPTH: BAKER SET @ 2980
PROD	5.5	3008	1475	
SURF	8.625	150		80 SX
T1	2.875	2980		

Well Type: SWD UIC Docket No: D30038.0 Date/Time to Plug: 10/24/2012 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: JOHN LACHENMAYR Company: LACHENMAYR OIL LLC Phone: (316) 283-5585

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2012 12:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

Perfs:

ON 10/24/2012 QUALITY WELL SERVICE MIRU, SANDED BACK TO 2939'. DUMPED 5 SX CEMENT TO CAP WITH BALER ON TOP OF SAND. SHOT OFF 5.5" PRODUCTION CASING @ 1475' AND PULLED. ON 10/25/2012 TAGGED TOP OF CMT @ 2730', PULLED PIPE TO 250' CIRCULATED 140 SX OF 60/40 POS MIX WITH 4% GEL TO SURFACE. CUT OFF CASING ABOUT 6' BELOW GROUND. JOB COMPLETE.

Remarks: QUALITY CEMENT TICKET #5572

Plugged through: CSG

District: 02

Signed

Daniel Fox
TECHNICIAN)
cc to MC 1/18/13

RECEIVED
JAN 17 2013
KCC WICHITA