

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-173-20684-00-01
 Spot: SWNESWNE Sec/Twnshp/Rge: 12-26S-1W
3443 feet from S Section Line, 1651 feet from E Section Line
 Lease Name: NEWTON Well #: 1
 County: SEDGWICK Total Vertical Depth: 3470 feet

Operator License No.: 6804
 Op Name: LACHENMAYR OIL LLC
 Address: PO BOX 526
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3401		
PLG		3401		
PROD 7		3454	711	300 SX
SURF 10.75		210		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2012 5:00 PM
 Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
 Proposal Rcvd. from: JOHN LACHENMAYR Company: LACHENMAYR OIL LLC Phone: (316) 283-5585

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 10/26/2012 12:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

ON 10/25/2012 QUALITY WELL SERVICE MIRU, SANDED BACK TO 3241'. DUMPED 7 SX CEMENT TO CAP WITH BALER ON TOP OF SAND. SHOT OFF 7" PRODUCTION CASING @ 711' AND PULLED. ON 10/26/2012 RAN PIPE TO 250' CIRCULATED 165 SX OF 60/40 POS MIX WITH 4% GEL TO SURFACE. TOPPED OFF W/10 SX, QUALITY CAME BACK CHECKED AND TOPPED OFF WITH 5 MORE SX OF DRY CEMENT. CUT OFF CASING ABOUT 6' BELOW GROUND. JOB COMPLETE.

Perfs:

Top	Bot	Thru	Comments
3431	3431	CSG	
3430	3431	CSG	
3358	3359	CSG	
3357	3359	CSG	

RECEIVED
 JAN 17 2013
 KCC WICHITA

Remarks: QUALITY CEMENT TICKET #5571

Plugged through: CSG

District: 02

Signed

Daniel G. Fox
 2/08/13 (TECHNICIAN)