

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21820-00-00
Spot: NESWNW Sec/Twnshp/Rge: 17-33S-2E
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: KREIDLER Well #: 17-5
County: SUMNER Total Vertical Depth: 3450 feet

Operator License No.: 30046
Op Name: JENKINS, DON(DECEASED)ESTATE
Address: 14711 296TH RD
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3446		125 SX
SURF	8.625	422		290 SX

✓/0
DONNIE JENKINS JR.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/28/2012 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Revd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE Phone: (620) 446-1381

Proposed
Plugging
Method:

CIBP ABOVE PERFS & 25 SKS CMT. PERFORATE CASING 470' & CIRC CEMENT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 12/28/2012 12:50 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 3300' & CAPPED WITH 2 SKS OF CEMENT. THE CASING WAS PERFORATED AT 470'. THE PUMP TRUCK, PUMPED CEMENT DOWN 5 1/2 AND BACK UP ANNULAS, WITH 175 SKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3360	3367	CSG	

Remarks: COPELAND ACID & CEMENT #41758. 60/40 4%. COMPLAINT

Plugged through: CSG

RECEIVED
JAN-07-2013

KCC WICHITA

District: 02

Signed _____

[Signature]

(TECHNICIAN)

✓/x