

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20066-00-00
Spot: W2E2SWSW Sec/Twnshp/Rge: 20-34S-7E
674 feet from S Section Line, 4514 feet from E Section Line
Lease Name: GAMMON Well #: 3
County: COWLEY Total Vertical Depth: 2682 feet

Operator License No.: 33711
Op Name: B-C STEEL, LLC
Address: 209 N FRY ST
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2682		110 SX
SURF	8.265	300		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/13/2012 8:00 AM
Plug Co. License No.: 34685 Plug Co. Name: RCCA WELL SERVICE, LLC
Proposal Rcvd. from: REX HORNING Company: BC STEEL LLC Phone: (620) 625-2999

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 12/14/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2590', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION & MIXED & PUMPED 12 BBL GEL FLUSH, 10 SXS CLASS A COMMON 2% CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2540'. RIH W/TBG @ 810', CONSOLIDATED MIXED & PUMPED 20 SXS CLASS A COMMON 2% CC AND DISPLACED IN CASING. SHOT SQUEEZE HOLES @ 350' 351' (4 HOLES). RIH W/TBG @ 350', CONSOLIDATED MIXED & PUMPED 90 SXS CLASS A COMMON 2% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12-14-2012 5:00 PM.

Perfs:

Top	Bot	Thru	Comments
2626	2636	CSG	


RECEIVED
JAN 08 2013
KCC WICHITA

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed


12/10/12 (TECHNICIAN)