

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20998-00-00
Spot: N2NW Sec/Twnshp/Rge: 29-27S-14W
4596 feet from S Section Line, 4064 feet from E Section Line
Lease Name: MILLER F Well #: 1
County: PRATT Total Vertical Depth: 4500 feet

Operator License No.: 33668
Op Name: M & S GAS, LLC
Address: 503 CANYON DR
LAWRENCE, KS 66049

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4494	2190	WITH 150 SX CMT
SURF	8.625	330		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/19/2012 8:30 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: BRAD TATRO Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: SAND BACK TO 4370' & PUT 4 SX CMT ON TOP OF CIBP. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/19/2012 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4210' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 907' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4443	4470		MISSISSIPPIAN
4423	4472		MISSISSIPPIAN

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED
DEC 21 2012
KCC DODGE CITY

Form CP-2/3

RECEIVED
JAN 07 2013
KCC WICHITA

RDW/P