

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21875-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 28-22S-21W
1982 feet from S Section Line, 2305 feet from W Section Line
Lease Name: SPARKS Well #: 1-28
County: HODGEMAN Total Vertical Depth: 4600 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	234		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/17/2013 11:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: KEN MCGUIRE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1410' WITH 50 SX CMT. 2ND PLUG AT 570' WITH 50 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 01/17/2013 12:45 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

1ST PLUG AT 1410' WITH 50 SX CMT. 2ND PLUG AT 570' WITH 50 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED

JAN 17 2013

KCC DODGE CITY

Signed

[Signature]
1/13 (TECHNICIAN)

RECEIVED
JAN 24 2013
KCC WICHITA

Handwritten initials