

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-06548-00-00
Spot: SESENW Sec/Twnshp/Rge: 31-18S-10W
3019 feet from S Section Line, 3141 feet from E Section Line
Lease Name: REIF B Well #: 1
County: RICE Total Vertical Depth: 3294 feet

Operator License No.: 30525
Op Name: LANGSTON, D. S.
Address: 310 W CENTRAL STE 202
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3253		200 SX
SURF	8	311		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/09/2013 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: THIS WELL HAD FAILED MIT FOR TA STATUS. SEE BELOW.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 01/11/2013 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

OPERATOR HAD TRIED TO SAND PERFS AND OH TO MIT THIS WELL. ESTIMATED TO HAVE DROPPED 600'-700' OF SAND. MIRU, ENCOUNTERED SAND OBSTRUCTION APPROX 15'. USED POWER SWIVEL AND PUMP TRUCK TO GET DOWN TO 2200'. CAP SAND WITH 5 SX'S CEMENT WITH DUMP BAILER. PERFORATE AT 1250', 900', AND 360'. RUN TUBING TO 1250' AND PUMP 35 SX'S CEMENT ON 1-9-13. LET SET, COME BACK ON 1-11-13, AND TAGGED CEMENT @ 950'. PULL TUBING TO 900' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 360' AND CIRCUALTE 160 SX'S CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3253	3295	OH	ARBUCKLE
2941	3200	CSG	LKC
2750	2756	CSG	LOWER TOPEKA

RECEIVED
JAN 24 2013
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #38143. LOG TECH #7331. THIS WELL PLUGGED DUE TO DENIED TA -- HFLD.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
1/11/13
(TECHNICIAN)