

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23847-00-00
Spot: NESWNESW Sec/Twnshp/Rge: 15-14S-12W
1950 feet from S Section Line, 1890 feet from W Section Line
Lease Name: DAVID BEISEL Well #: 1
County: RUSSELL Total Vertical Depth: 3350 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	366		200 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/08/2013 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: JAY Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-4477

Proposed Plugging Method: Ordered 190 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 01/08/2013 7:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st plug @3254 w/25 sx
2nd plug @675 w/25 sx
3rd plug @450 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

RECEIVED
JAN 16 2013
KCC WICHITA

District: 04

Signed Richard Williams
1/8/13 (TECHNICIAN) CM

JAN 10 2013