

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22038-00-00
Spot: NENENESE Sec/Twnshp/Rge: 13-7S-18W
2909 feet from N Section Line, 325 feet from E Section Line
Lease Name: SMITH Well #: 1
County: ROOKS Total Vertical Depth: 3387 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	92		100 SX
PROD	5.5	3385		150 SX
SURF	8.625	1285		425 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2012 10:00 AM
Plug Co. License No.: 34093 Plug Co. Name: SUMMIT WELL SERVICE LLC
Proposal Rcvd. from: ROLAND NYP Company: RGN COMPANY Phone: (785) 737-3242

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 10 sx gel spacer and 500 # hulls.
Backside squeezed with 225 sx cement between 5 1/2" and 8 5/8" casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/21/2012 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3200' and pumped 10 sx gel followed by 75 sx cement.
Pulled tubing to 1700' and pumped 200 sx cement to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 60 sx cement.
Hooked to 8 5/8" x 5 1/2" annulus and pressured up immediately.

GPS: 39.44299 -099.26919

Perfs:

Top	Bot	Thru	Comments
3336	3339		

RECEIVED
DEC 31 2012
KCC WICHITA

Remarks: BASIC ENERGY SERVICES TICKET # 07084

Plugged through: TBG

District: 04

Signed

1/03/13

Pat Bedore
(TECHNICIAN)

CM

DEC 26 2012