

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20781-00-00
Spot: N2S2SWNW Sec/Twnshp/Rge: 23-30S-18W
2218 feet from N Section Line, 656 feet from W Section Line
Lease Name: UNRUH CURTIS Well #: 1-A
County: KIOWA Total Vertical Depth: 5128 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5100		
PROD	5.5	5106	2000	WITH 250 SX CMT
SURF	8.625	518		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/14/2012 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 5000' & 5 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 530' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/14/2012 11:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SANDED TO 5000' & 5 SX CMT. 1ST PLUG AT 1130' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 536' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5106	5128		
5080	5086		

RECEIVED
DEC 26 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed

[Signature]

(TECHNICIAN)

RECEIVED

DEC 18 2012

KCC DODGE CITY

[Handwritten mark]