

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00621-00-00
Spot: SENWSE Sec/Twnshp/Rge: 24-22S-36W
1702 feet from S Section Line, 1570 feet from E Section Line
Lease Name: CAMPBELL VAN DOREN Well #: 1
County: KEARNY Total Vertical Depth: 2600 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| PROD | 7 | 2548 | 0 | WITH 700 SX CMT |
| SURF | 10.75 | 218 | | WITH 175 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/18/2012 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL Phone: (620) 272-1025

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/18/2012 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PLUG BACK OPEN HOLE FROM 2600' TO 2540' WITH SAND. TAGGED WITH TBG.
SPOT 30 SX CMT WITH 200# HULLS @ 2540'. PLUG AT 2121' WITH 75 SX CMT.
PLUG AT 918' WITH 75 SX CMT. PLUG AT 245' WITH 40 SX CMT. DIG OUT
ANNULUS & FOUND IT FULL OF CMT TO THE TOP.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2548 | 2600 | OH | |

RECEIVED
JAN 11 2013
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
12/18/12
(TECHNICIAN)

RECEIVED

DEC 27 2012

KCC DODGE CITY

BMZ