

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-21161-00-00  
Spot: W2NENENW Sec/Twnshp/Rge: 25-14S-30W  
4950 feet from S Section Line, 2980 feet from E Section Line  
Lease Name: GROOM Well #: 1  
County: GOVE Total Vertical Depth: 4450 feet

Operator License No.: 5420  
Op Name: WHITE & ELLIS DRILLING, INC.  
Address: PO BOX 48848  
WICHITA, KS 67201

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 4.5   | 4447       |             | 175 SX   |
| SURF   | 8.625 | 307        |             | 175 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/10/2012 11:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: DALLAS FLOWERS Company: WHITETAIL CRUDE, INC Phone: (316) 321-0550

Proposed Plugging Method: 8 5/8" Surface casing set at 307' w/175 sx cement. 4 1/2" production casing set at 4447' w/175 sx cement. Port Collar at 2114' w/400 sx cement. TD at 4450'. PBSD 4447'. Perforations: 4165'-4208', 4312' - 4316'. Ordered 400 sx 60/40 pozmix 4% gel w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/10/2012 3:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4200'. Connected to tubing and pumped 150 sx cement w/300 # hulls.  
Pulled tubing to 2100'. Connected to tubing and pumped 150 sx cement w/200 # hulls.  
Cemented to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 35 sx cement. Maximum pressured 250 psi.  
Connected to 8 5/8" surface casing. Immediate pressure up to 500 #.

GPS: 38.81475 -100.60586

Perfs:

Remarks: SWIFT SERVICES TICKET # 23513

Plugged through: TBG

District: 04

Signed Darrel Dipman  
12/10/12 (TECHNICIAN)

CM

DEC 13 2012

Form CP-2/3

RECEIVED  
DEC 19 2012  
KCC WICHITA