

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20654-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 6-35S-26W
589 feet from N Section Line, 589 feet from E Section Line
Lease Name: EDIGER Well #: 1-6
County: MEADE Total Vertical Depth: 6300 feet

Operator License No.: 8060
Op Name: ZENERGY, INC.
Address: 6100 S YALE STE 1700
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4650		WITH 2 SX CMT
CIBP		5680		WITH 2 SX CMT
PROD 4.5		6299	0	WITH 300 SX CMT
SURF 8.625		1463		WITH 700 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/10/2012 9:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: STEVE HELM Company: ZENERGY Phone: (620) 482-0453

Proposed Plugging Method: SET CIBP @ 5680' WITH 2 SX CMT. SET CIBP @ 4650' WITH 2 SX CMT. PERFORATE @ 1470' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 12/10/2012 1:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 5680' WITH 2 SX CMT. SET CIBP @ 4650' WITH 2 SX CMT. PERFORATE @ 1480' & PUMPED 300 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5895	5926		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

Richard M. Lacey
12/13

(TECHNICIAN)

RECEIVED

DEC 18 2012

KCC DODGE CITY

RECEIVED
DEC 20 2012
KCC WICHITA

BONY