

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-21148-00-00
Spot: NENWSE Sec/Twnshp/Rge: 23-11S-33W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: NICKELSON Well #: 1-23
County: LOGAN Total Vertical Depth: 4657 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	342		240 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/29/2013 12:00 AM
Plug Co. License No.: 6039 Plug Co. Name: L. D. DRILLING, INC.
Proposal Rcvd. from: RICK Company: L. D. DRILLING, INC. Phone: (620) 617-4794

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 01/29/2013 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st plug @2645 w/25 sx
2nd plug @1321 w/100 sx
3rd plug @400 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: CONSOLIDATED

Plugged through: DP

RECEIVED
FEB 04 2013
KCC WICHITA

District: 04

Signed [Signature]
2/08/13 (TECHNICIAN) CM

JAN 29 2013