

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-06138-00-00
Spot: W2W2SENE Sec/Twnshp/Rge: 18-11S-17W
1980 feet from N Section Line, 1065 feet from E Section Line
Lease Name: KOLLMAN Well #: 11
County: ELLIS Total Vertical Depth: 3450 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 1900 N. AMIDON, STE 210
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3273		
CIBP		3352		
CIBP		3397		
PROD	5.5	3449		250 SX
SURF	9.625	214		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2013 10:00 AM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Revd. from: RANDY WEIGEL Company: EMPIRE ENERGY E&P LLC Phone: (785) 737-3736

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations at 3121' - 3123'; 3181' - 3183; 3342' - 3348'; 3356' - 3380'; 3401' - 3413'.
1967- Squeezed perms 3411' - 3413'.
1985- Squeezed 360' - 404' w/500 sx cement.
Squeezed 360' - 404' w/400 sx cement. CIBP at 3274'.
Milled on well for 5 days. Casing leaks on well
GPS: 39.09761 -099.24464

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2013 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf-Tech perforated at 1650' and 1090'.
APS ran in hole with tubing to 3154'. Consolidated rigged to tubing and mixed and pumped 165 sx cement w/300 # hulls mixed in.
Pulled tubing to 1632'. Consolidated rigged to tubing and mixed and pumped 165 sx cement w/300 # hulls mixed in to circulate cement to surface.
Rigged to 5 1/2" casing with a swedge and pumped 12 sx cement to pressure with 250 psi and 250 psi shut in pressure.
9.625' casing was dug up previously. Operator stated Pat Bedore gave ok on cement on backside.

Perfs:

Top	Bot	Thru	Comments
3401	3413		
3356	3380		
3342	3348		
3181	3183		
3121	3123		

RECEIVED
FEB 01 2013
KCC WICHITA

Remarks: CONSOLIDATED OILWELL SERVICES LLC TICKET # 39293

Plugged through: TBG

District: 04

Signed [Signature]
2/02/13 (TECHNICIAN)

JAN 25 2013

CM