

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22657-00-01  
Spot: NWSEWSW Sec/Twnshp/Rge: 29-7S-19W  
350 feet from S Section Line, 4370 feet from E Section Line  
Lease Name: STICE Well #: 1  
County: ROOKS Total Vertical Depth: 1480 feet

Operator License No.: 34151  
Op Name: BRINKER ENTERPRISES, LLC  
Address: 216 S MARSHALL ST  
GLEN ELDER, KS 67446

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	69	0	w/130sx
PROD	5.5	1416	0	350 SX
SURF	8.625	1446	0	400 SX

Well Type: SWD UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/28/2012 8:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: PRESTON DREILING Company: BRINKER ENTERPRISE Phone: \_\_\_\_\_

Proposed  
Plugging  
Method:

Ordered 250 sx 60/40 pozmix 4% gel cement w/400 # hulls.  
Perforated Cedar Hills at 1090' - 1140'. Flowing salt water 5" above casing. Shut in 5 1/2" with 25 psi.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/28/2012 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1085'. SOS Pumped 65 sx cement followed by 65 sx cement w/100 # hulls.  
Circulated cement out 5 1/2" casing. PTOH. Pumped 25 sx cement. Max pressure 300 psi.  
Shut in pressure 300 psi.  
Hooked up to backside and pumped 15 sx cement. Max pressure 250 psi. Shut in pressure 250 psi.

Perfs:

Top	Bot	Thru	Comments
1090	1140		

RECEIVED  
JAN 08 2013  
KCC WICHITA

Remarks: GPS: 39.40963, -099.47012

Plugged through: TBG

District: 04

Signed Richard Williams  
1/9/13 (TECHNICIAN)  
cc to VMC 1/09/13

CM

JAN 04 2013