

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25754-00-00
Spot: SESWSENE Sec/Twnshp/Rge: 9-19S-12W
2350 feet from N Section Line, 850 feet from E Section Line
Lease Name: HAMMEKE - MARY S UNIT Well #: 1-9
County: BARTON Total Vertical Depth: 3434 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3430		210 SX
SURF	8.625	310		300 SX
T1	2.375	3180		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/04/2013 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMANN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/04/2013 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations. Topped with 4 sx cement.
Cut casing at 2470'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls.
Pulled casing to 675' and pumped 40 sx cement w/100 # hulls.
Pulled casing to 350'. Circulated cement to surface w/100 sx cement w/100 # hulls.
GPS: 38.41369 -098.64881

Perfs:

Top	Bot	Thru	Comments
3327	3330		
3288	3290		
3194	3198		

RECEIVED
JAN 16 2013

Remarks: COPELAND ACID AND CEMENTING

KCC WICHITA

Plugged through: CSG

District: 04

Signed Bruce Rodie
2/18/13 (TECHNICIAN) CM

JAN 10 2013