

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23644-00-00
Spot: NESENE SW Sec/Twnshp/Rge: 11-21S-12W
1786 feet from S Section Line, 2961 feet from E Section Line
Lease Name: KAREN Well #: 1-11
County: STAFFORD Total Vertical Depth: 3640 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3350		
PROD	5.5	3639	2250	WITH 180 SX CMT
SURF	8.625	329		WITH 375 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/12/2012 8:15 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 3200' & 5 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI Witness Type: NONE
Date/Time Plugging Completed: 11/12/2012 9:40 AM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

SAND TO 3204' & 5 SX CMT. 1ST PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3540	3544		
3256	3260		

RECEIVED
FEB 04 2013
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed: Richard W. Fay
2/05/13 (TECHNICIAN)

RECEIVED
JAN 31 2013
KCC DODGE CITY

RWJ